



GENESEE COUNTY HIGHWAY DEPARTMENT  
153 CEDAR STREET  
BATAVIA, NEW YORK 14020

---

**GENESEE COUNTY WATER SUPPLY PROJECT: UPCOMING PHASE 3 PROJECTS**  
**January 2024**

The subprojects listed below are several candidates to be constructed early on in Phase 3 of the Countywide Water Supply Project. Phase 3 has a total of 11 subprojects that include transmission mains, water storage tanks, pump stations, and water quality improvements to convey an additional 7.6 Million gallon per day (MGD) to Genesee County.

**North Road Water Storage Tank**

- Location: LeRoy, New York (adjacent to existing North Road Pump Station)
- Project Description: Construction of a new 1.0 million gallon ground level water storage tank to provide redundancy in storage, firefighting response, and stabilize pressures at the North Road Pump Station.
- Cost: **\$4,640,000**
- Grants: \$2,000,000 award (FY23 Congressionally Directed Spending Request)

**Golden Road Transmission Main and Pump Station Upgrades**

- Location: Chili/Gates, New York
- Project Description: Installation of a new 36" transmission main, approximately 30,000 linear feet in length. This large main will have a 13.6 MGD capacity.
- Cost: **\$21,848,000**
- Grants: None

**Stottle Road Transmission Main**

- Location: Chili, New York
- Project Description: Installation of a new 30" transmission main approximately 19,000 linear feet in length and convey an additional 4.61 MGD.
- Cost: **\$13,444,000**
- Grants: None

**Macomber Road and Galloway Road Water Main**

- Location: Town of Batavia, New York
- Project Description: Installation of approximately 11,300 linear feet of 12" PVC water main along Galloway Rd. and approximately 3,400 linear feet of 8" PVC water main along Macomber Rd.
- Cost: **\$2,522,000**
- Grants: None